

CAPE MAY COUNTY
DEPARTMENT OF PUBLIC WORKS
Office of the COUNTY ENGINEER



DANIEL BEYEL
Freeholder

DALE M. FOSTER
Engineer

4 Moore Road
Cape May Court House, N.J. 08210-1601
(609) 465-1035 Fax: (609) 465-1418
E-mail: countyengineer@co.cape-may.nj.us
Website: www.capemaycountygov.net

May 27, 2011

Memo To: Prospective Bidders

From: Dale M. Foster, PE, County Engineer

Re: **REPLACEMENT OF CHILLER UNIT AT THE COUNTY OF CAPE MAY
CORRECTION FACILITY
ADDENDUM NO. 2**

Addendum No. 2 has been issued to the Contract Documents for the referenced project. The revision listed shall be made to the Contract Documents issued for the receipt of bids. This addendum shall become part of the total contract.

The Bidder shall acknowledge receipt of this Addendum by signing and returning the attached acknowledgement sheet with the Bidder's Proposal.

The County regrets any inconvenience that this Addendum causes.

DMF/df
Enclosures

Cc: Stephen O'Connor, Clerk/Administrator
Purchasing Department

ADDENDUM NO. 2

The revisions listed below shall become part of the contract, due consideration to these revisions shall be made by the Contractor in preparing his bid for the project. The Contractor shall acknowledge receipt of this Addendum by signing and returning the attached sheet with the Contractor's Proposal. Proposals not including a signed copy of the attached sheet will not be considered.

THE FOLLOWING CHANGES/CLARIFICATIONS SHALL BE MADE TO THE TECHNICAL SPECIFICATIONS.

1. **CLARIFICATION:** All contractors regardless if they are equipment or controls dealers are eligible to submit bids for the referenced project.
2. **CLARIFICATION:** The contract is for replacing the existing chiller with a new chiller as specified. The controls would be set up per the existing chiller.
3. **ADDITION:** Contractor to add two (2) full size valved ports at the point of connection to for extending the chilled water supply and return piping to the new chiller. Purpose for the ports is to connect an emergency chiller in case of a primary chiller unit failure. Add two (2) valves to isolate the chiller from the new valved ports for emergency use. All ports shall be full piping size. All valves shall be flanged, butterfly type, with notched locking lever operators and full flanges. Valves shall be as manufactured by Nibco FC-27, American VMC-2004-LS, Apollo LC 149-04-1 or equivalent valves manufactured in the USA.

**STEPHEN O'CONNOR,
CLERK/ADMINISTRATOR**

**DANIEL BEYEL,
FREEHOLDER DIRECTOR**

ADDENDUM NO. 2 ACKNOWLEDGEMENT

Acknowledgement is hereby made of Addendum No. 1, issued on May 12, 2011, received since the issuance of the Contract Documents for **REPLACEMENT OF CHILLER UNIT AT THE COUNTY OF CAPE MAY CORRECTION FACILITY** located at 125 Crest Haven Road, Cape May Court House, NJ. The Contractor shall include this signed sheet with his bid package.

Signature of Bidder: _____

Title: _____

Name of Firm: _____

Address: _____

Date: _____